

SECTION 11 00 00 - EQUIPMENT

PART 1 - GENERAL

1.1 SYSTEM REQUIREMENTS

- A. Design Requirements:
 - 1. Provide drains at all dock levelers.
 - 2. Fixed and Movable Equipment:
 - a. Fixed equipment shall generally be furnished and installed by the General Contractor as part of the construction contract.

PART 2 - PRODUCTS

2.1 ICE FLAKER

- A. Basis-of-Design Product: Subject to compliance with requirements, provide Ice-O-Matic; EF-250-A-32S or a comparable product by one of the following:
 - 1. Crystal Tips.
 - 2. Scotsman.
- B. Free Standing Ice Flaker Unit
 - 1. Size: Approximately 32 inches wide, 41 inches high, 28 inches deep.
 - 2. Storage Capacity: Minimum 140 lb. self-contained insulated storage bin.
 - 3. Production Capacity: Minimum 400 lbs. of ice per 24 hour period at ambient room air temperature of 70 deg F and a water inlet temperature of 50 deg F.

PART 3 - EXECUTION (Not Applicable)

END OF SECTION 11 00 00