

SECTION 31 20 00 - EARTH MOVING

PART 1 - GENERAL

1.1 REFERENCES

- A. Asbestos-Contaminated Soil Management, Standard Operating Procedure Document, Version 1, February 26, 2010.
 - 1. Refer to Section 02 81 00 – Transportation/Disposal of Hazardous Material, Part 4.

1.2 SYSTEM PERFORMANCE REQUIREMENTS

- A. Performance Requirements
 - 1. Backfilling:
 - a. Backfill excavations as promptly as work permits, but not until completion of inspection, testing, approval, and location recording of underground utilities.
 - b. Concrete tailings, sand, gravel and other debris are not permitted in trenches.
 - c. Consult the University Project Manager immediately for direction with uncharted or incorrectly charted piping or other utilities encountered during excavation. Cooperate with the University Project Manager in keeping respective services and facilities in operation. Repair damaged utilities to the satisfaction of the University Project Manager.
 - 2. Excavations:
 - a. Surround all excavations exceeding 6 ft in depth with a 6 feet high chain link fence system.
 - b. Provide an Environmental Health and Safety (EHS) trained spotter on site for identifying asbestos contaminated soil.

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION (Not Applicable)

END OF SECTION 31 20 00